

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20786-00-00
Spot: E2SESE Sec/Twnshp/Rge: 18-12S-15W
660 feet from S Section Line, 330 feet from E Section Line
Lease Name: MERMIS Well #: 6
County: RUSSELL Total Vertical Depth: 2585 feet

Operator License No.: 34518
Op Name: BASGALL OIL LLC
Address: 1403 W 44TH ST.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2585		
SURF	8.625	101		75 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2016 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: BRAD BASGALL Company: BASGALL OIL LLC DBA Phone: (785) 650-1809

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/600 # hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2016 9:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

09/21/2016 - Perforated at 1500', 550' and 110'. Ran tubing to 2440' and tagged bottom. Pulled tubing to 2420' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1100' and pumped 75 sx cement w/200 # hulls. Slight blow on backside. POOH. Shut down.
09/22/2016 - Ran tubing in and tagged top of cement at 155'. Pulled tubing to 150' and pumped 30 sx cement. Cement circulated to pit. POOH. Hooked to braden head and pumped 20 sx cement. Cement circulated out of 4 1/2" casing.

GPS: 39.00391 -099.02137

Perfs:

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENTING TICKET # 1779 AND 7831

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

PM

SEP 27 2016

OCT 14 2016

no

Form CP-2/3