

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-30172-00-00
Spot: SESESE Sec/Twnshp/Rge: 4-14S-17W
339 feet from S Section Line, 472 feet from E Section Line
Lease Name: REGINA LEASE Well #: 2
County: ELLIS Total Vertical Depth: 3580 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

PROD 4.5 3580 150 SX

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

SURF 8.625 173 135 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/13/2016 8:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: CURT GAGEL

Company: BEREXCO LLC

Phone: (785) 623-0546

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3557' - 3572' ARB
Tubing stuck in hole at 3103' with a packer in hole.

Plugging Proposal Received By: PAT STAAB

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/13/2016 3:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Berexco ran in hole and removed retrievable plug at 3075'. Perf Tech perforated at 1650', 1220' and 630'. Berexco ran in hole with tubing to 3015'. Global rigged to tubing and pumped 100 sx cement w/300 # hulls mixed in. Pulled tubing to 1650'. Rigged to tubing and pumped 75 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 25 sx cement to pressure with 325 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface casing with instant pressure.

GPS: 38.85764 -099.20807

Perfs:

Top	Bot	Thru	Comments
3557	3572		


Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: BLOBAL CEMENTING CO. TICKET # 2703

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Ch

SEP 15 2016

OCT 14 2016
700

Form CP-2/3