

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40206-00-00
Spot: W2NWSE Sec/Twnshp/Rge: 8-28S-4E
1980 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HAINES WEST Well #: 3
County: BUTLER Total Vertical Depth: 2442 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2431		65 SX
SURF	7	2431		65 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2016 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO. Phone: (31) 637-1954

Proposed Plugging Method: Per KCC recommendations

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH w/tbg @ 2400', Consolidated Oil Well Services mixed & pumped 50 sxs 60/40 pozmix 4% gel 3% cc & displaced in casing. Waited 2 hours, tagged cement @2253'. RIH on wireline, perforated squeeze holes @ 250' - 251' (4 holes). RIH w/tbg @ 260', Consolidated Oilwell Services established circulation, mixed & pumped 195 sxs 60/40 pozmix 4% gel 2% cc to surface. Cement circulated. Consolidated cement ticket #51426.

Top	Bot	Thru	Comments
2431	2442	OIL	

Remarks: COMPLIANCE/TA'S

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

OCT 14 2016
Form CP-2/3

JK
DK