

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40210-00-00
Spot: N2SENV Sec/Twnshp/Rge: 11-27S-5E
3630 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KNUTSON Well #: 1
County: BUTLER Total Vertical Depth: 2718 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2480		225 SX
PROD	5.5	2690		
SURF	8.625	154		
SURF	5.5	2690		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2016 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO Phone: (31) 637-2954

Proposed Plugging Method: Per KCC recommendations.

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 09/13/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH w/ tbg @ 2700', Hurricane Services mixed & pumped 20 sxs 60/40 pozmix 4% gel 3% CC & displaced in casing. Waited 2 hours, tagged cement @ 2610'. RIH on wireline, perforated squeeze holes @ 250' - 251' (4 holes). RIH w/tbg on @ 260', Hurricane Services established circulation, mixed & pumped 110 sxs 60/40 pozmix 4% gel 2% CC to surface. Cement circulated. Hurricane cement ticket #100672.

Top	Bot	Thru	Comments
2690	2718	OH	

Remarks: COMPLIANCE/TA'S

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

OCT 14 2016
Form CP-2/3
no

✓