

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rody of Rains & Williamson has this
date requested permission to plug the following described well:

Mr. Rody guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 435 Page Court, Wichita, Kansas

Lease Name: Giessel Well No. 1

Location: C SE SW Sec. 26 Twp. 25 Rge. 22 (E) (W)

County: Ford Total Depth 4915' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rody was instructed to plug the well as follows:


8 5/8" to 238' circulated w/ cement. Mud 4915' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 240'

Spot 35 sacks cement 240' to 140' Mud 140' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent