

15-057-10012-6000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walker of Mull Drilling Co. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Indiek Well No. 1

Location: NE SE SE Sec. 25 Twp. 25 Rge. 22 (E) (W)

County Ford Total Depth 4915' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

- 8 5/8" to 247' circulated w/ cement. T.D. 4915'
- Mud 4915' to 700' Spot 30 sacks cement 700' to 600'
- Mud 600' to 297' Spot 35 sacks cement 297' to 197'
- Mud 197' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edwin J. Eves
Conservation Division Agent