

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

10 April 1982

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To be filed by Logging Agent)

APR 13 1982
15-057-20261
CONSERVATION DIVISION
Wichita, Kansas

4-13-82

Dear Sir:

Mr. Leon Strecker of Abercrombie Drilling Inc. has this date requested permission to plug the following described well:

Operator's Full Name: F. M. Oil Co.

Complete Address: Union Center Bldg, 150 N. Main Suite 422 Wichita Kansas 67202

Lease Name: Thomas Well No. _____

Location: C-SE-NE Sec. 2 Twp. 25 Rge. 22 (E) (W)

County: Ford Total Depth: 4825'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Strecker was instructed to plug the well as follows:

The anhydrite was topped at 1520', 1st plug at 1500' with 60 bbls of cement. 2nd plug push rubber plug to 358' & pumped 40 bbls on top of it. 3rd plug 40' to 0' on solid bridge with 10 bbls of cement. Then circulated 10 bbls of cement in rat hole. The cement was pumped through drill pipe with hole full of heavy mud. The cement used was common with 2 1/2" all 5% c.c. Seem Cementing accomplished the plugging. There was 369' of 8 1/2" surface casing cement circulated.

Very truly yours,

Paul A. Luthi
Conservation Division Agent