

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

NOV 10 1965

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Walker of Mull Drilling Co., Inc. has this  
 date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Co., Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Rosa De Muth Well No. # 1

Location: C SW NE Sec. 9 Twp. 25S Rge. 22 (E) (W)

County Ford Total Depth 4925 Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Walker was instructed to plug the well as follows:

8 5/8" - 290' Circulated w/cement.

Mud 4925' to 700' Spotted 25 Sax. cement 700' to 625'

Mud 625' to 300' Spotted 25 Sax. cement 300' to 225'

Mud 225' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

*Hugh Scott*  
 Conservation Division Agent