



15-057-00112-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Unruch of Donald C. Slawson has this
date requested permission to plug the following described well:

Mr. Unruch guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 407 One Twenty Building, Wichita, Kansas

Lease Name: Tassett Well No. A-1

Location: C NW SE Sec. 10 Twp. 25 Rge. 22 (W)

County Ford Total Depth 4932' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Unruch was instructed to plug the well as follows:

8 5/8"-303' Circulated w/cement. 4 1/2"-4932' Cemented.

Perforations 4791' to 4799'. Plug back to 4815'

Sand bottom 4815' to 4775' Spotted 5" sax. cement 4775' to 4715'

Mud 4715' to 310' 35 Sax. cement 310' to 210'

Mud 210' to 55'. Rock bridge 55' to 45'. 15 Sax. cement 45' to 0

Very truly yours,

Conservation Division Agent