

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1966
7-13-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Rod Sweetman of S & S Drilling Company has this date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name: Whitner "A" Well No. # 1

Location: C SW SW Sec. 9 Twp. 30 Rge. 9 (E)(W) W

County Kingman Total Depth 4435' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

278' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent