



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Valentine of LVO has this

date requested permission to plug the following described well:

Mr. Valentine guarantees payment of the plugging fee.

Operator's full Name: LVO Corporation

Complete Address: Box 2848, Tulsa, Oklahoma

Lease Name: Unit 0720 Well No. 1

Location: C NE SW Sec. 7 Twp. 22 Rge. 40 (E) (W)

County: Hamilton Total Depth 2752' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole SWD

Mr. Valentine was instructed to plug the well as follows:

8 5/8" to 312' circulated w/ cement . 4 1/2" to 2752' cemented.


Top perforations 2720' Plug bottom w/ 20 sacks cement.

Top of cement 2506' Mud 2506' to 320'

Spot 45 sacks cement 320' to 200' Mud 200' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent