



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Okmar Oil Company has this
date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company

Complete Address: 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name: Imel Well No. 2

Location: C NW SW Sec. 11 Twp. 25 Rge. 22 (E)(W)

County: Ford Total Depth 4830' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Norwood was instructed to plug the well as follows:

8 5/8" to 280' circulated w/ cement. Mud 4830' to 660'

Spot 70 sacks cement 660' to 400' Mud 400' to 240'

Spot 20 sacks cement 240' to 160' Mud 160' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent