

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1973 6-1-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of Mull Drilling has this

date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.Operator's full Name: Muñl Drilling Co.Complete Address: 415 Page Court, Wichita, KansasLease Name: Demuth Well No. 1Location: C NW SE Sec. 11 Twp. 25 Rge. 22 (E) (W)County: Ford Total Depth 4795' Oil WellGas Well Input Well SWD Well D & A Lost Hole Mr. Delaney was instructed to plug the well as follows:8 5/8" to 366' cirul ted w/ cement. Mud 4795' to 700'Spot 35 sacks cement 700' to 600' Mud 600' to 350'Spot 35 sacks cement 350' to 250' Mud 250' to 45'Plug, Hulls @ 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Evers
Conservation Division Agent