

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202


WELL PLUGGING RECORD

Stafford County, Sec. 26 Twp. 24 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines C N/2 NE SE
Lease Owner Woodman & Iannitti Drilling Company
Lease Name Jordan Well No. 1
Office Address 706 Union Nat'l. Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 23 19 71
Application for plugging filed Oct. 23 19 71
Application for plugging approved Oct. 23 19 71
Plugging commenced Oct. 23 19 71
Plugging completed Oct. 23 19 71
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3941 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	279	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug @ 600 w/40 sx.
2nd plug @ 250 w/25 sx.
3rd plug @ 40 w/10 sx.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1971
CONSERVATION DIVISION
Wichita, Kansas
10-27-71

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Woodman & Iannitti Drilling Company
Address 706 Union National Bldg.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. T. WOODMAN (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
706 Union Nat'l. Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 71

My commission expires Feb. 11, 1972
Justina Chamberlain
Justina Chamberlain Notary Public.

K. T. WOODMAN
Res. PHONE AM 5-3572
OFFICE PH. AM 5-7650
WICHITA, KANSAS**WOODMAN & IANNITTI DRILLING COMPANY***Rotary Drilling Contractors*

706 UNION NATIONAL BUILDING

WICHITA, KANSAS 67202

October 27, 1971

Company;	Woodman & Iannitti Drilling Co.
Farm;	#1 Jordan
Location;	Stafford
Section;	26-24-12W
Comm;	October 13, 1971
Compl;	October 23, 1971
Contractor;	Woodman & Iannitti Drilling Co.
Total Depth;	3941
Casing;	8 5/8" at 279
Production;	D & A

Figures Indicate Bottom Of Formations:


40	Clay & Sand
279	Sand & Shale
334	Shale
407	Red Bed
649	Red Bed
664	Anhy
1230	Red Bed & Shale
1675	Shale
1800	Lime & Shale
2025	Lime
2100	Lime & Shale
2210	Shale & Lime
2400	Lime & Shale
2570	Shale
2730	Shale & Lime Streaks
2920	Lime & Shale
3065	Lime & Shale
3150	Lime & Shale
3255	Lime & Shale
3324	Lime & Shale
3345	Lime
3470	Shale & Lime
3540	Lime
3565	Lime
3645	Lime
3790	Lime
3835	Lime
3890	Lime
3921	Lime
3924	Chert
3927	Lime & Chert
3941	Lime & Chert

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1971

CONSERVATION DIVISION
Wichita, Kansas

Woodman & Iannitti Drilling Co.


K. T. Woodman