

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 18 TWP. 24S RGE. 13 W
Location as in quarters or footage from lines:
C SE SW NE

		18	

Locate Well
correctly on above
Section Pratt.

Lease Owner Texas Energies, Inc.
Lease Name Rixon Well No. 1-18
Office Address P.O. Box 947 Pratt, KS 67124
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 9-09-82
Application for plugging filed _____
Plugging commenced 9-08-82
Plugging completed 9-09-82
Reason for abandonment of well or producing formation _____
Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi (as per verbal order)
Producing formation -- Depth to top -- bottom -- T.D. 4250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	266	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged well with 130 sxs 50-50 poz 4% Gel 3% CC as follows:
cement plug at 720' with 60 sxs
cement plug at 360' with 40 sxs
solid bridge plug at 40' with 1/2 sxs hulls, wood and rubber
plug and 10 sxs
rathole with 12-15 sxs
water well with 5 sxs

Plug at 40' did not hold. Ran new plug with 1 yard of Ready Mix

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wheatstate Drilling


STATE OF Kansas COUNTY OF Pratt, ss.

E. H. Bittner (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) E. H. Bittner
P.O. Box 947 Pratt, KS 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 82

My Commission expires: April 23, 1983



RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

SEP 21 1982
9-21-82
CONSERVATION DIVISION
Wichita, Kansas