


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

KINGMAN County. Sec. 1 Twp. 30S Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW, NE, NE
Lease Owner ALADDIN PETROLEUM CORPORATION
Lease Name SHATELL Well No. 1
Office Address 809 Petroleum Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 27, 1959
Application for plugging filed September 28, 1959
Application for plugging approved September 28, 1959
Plugging commenced September 28, 1959
Plugging completed September 28, 1959
Reason for abandonment of well or producing formation No productive zone.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well FRED HAMPEL
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4529 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					none	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Gunned pits forming heavy mud, filled hole up to 240' with heavy mud, pushed plug & 1/4 sx. hulls to 240', cap with 18 sx. cement through drill pipe.
Filled hole up to 40', pushed wooden plug & 1/4 sx. hulls to 40', filled hole up to base of well cellar with 10 sx. cement.

STATE CORPORATION COMMISSION
AUG 10 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
VERNE A. MORRIS (employee of owner) ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Verne A. Morris
Route #2, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1960

My commission expires November 12, 1962
Brantburg Notary Public.

WELL LOG

COMPANY ALADDIN PETROLEUM CORPORATION

SEC. 1 T-30S R. 9W

FARM SHATELL NO. 1

LOC. NW, NE, NE


TOTAL DEPTH. 4529'

COUNTY KINGMAN CO., KANSAS

COMM. September 23, 1959 COMP. September 28, 1959

CONTRACTOR GARVEY DRILLING COMPANY

CASING OLD HOLE WASH-DOWN
(8-5/8" set at 251')



ELEVATION 1568 GL

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

OLD HOLE WASH-DOWN & DEEPEN

0 - 4221'	Open hole
4223	Lime
4269	Shale & lime
4328	Lime
4340	Lime & chert
4403	Shale
4465	Lime & shale
4500	Shale & lime
4529	Viola lime
4529	T. D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1960
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 SHATELL well

Verne A. Morris

Subscribed and sworn to before me this 4th day of August 19 60

My Commission Expires: November 12, 1962

[Signature]
NOTARY PUBLIC