

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
July 2014
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30252
Name: patteson oil
Address 1: p.o. box 177
Address 2: _____
City: MOLINE State: KS. Zip: 67353 + 0177
Contact Person: TOM PATTESON
Phone: (620) 647-3203
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: 1983 Bottom: 1985 T.D. 2010
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 015-019-20247-00-00
Spot Description: _____
NE SE Sec. 23 Twp. 32 S. R. 10 East West
3,630 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: CHAUTAQUA
Lease Name: SHAFFER-E Well #: 6
Date Well Completed: 7-31-71
The plugging proposal was approved on: _____ (Date)
by: DUANE SIMS (KCC District Agent's Name)
Plugging Commenced: 8-14-16
Plugging Completed: 8-15-16

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8-5/8	40	NO
MISSISSIPPI	OIL-WATER	PRODUCTION	4-1/2	2025	NO

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

ran 1" tubing to 1950 -gel hole-cemented with 15 sacks Pulled 1" out perforated casing at 1000' and 550' Ran 1" tubing to 1000' Cement with 25 sacks. Pulled 1' and up to 550'. Cemented to surface with 194 sacks closed pit.

KCC WICHITA
OCT 13 2016
RECEIVED

Plugging Contractor License #: 32884 Name: Elmore's, Inc.
Address 1: 419 South Montgomery Address 2: P. O. Box 87
City: Sedan State: Kansas Zip: 67361 + 1927
Phone: (620) 725-5744
Name of Party Responsible for Plugging Fees: Patteson Oil
State of Kansas County, Elk, ss.
Tom J. Patteson Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tom J. Patteson

MS
10-17-16