


Give All Information Completely
Make Required Attachments
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 1 Twp. 30 Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Zrubek Well No. 1
Office Address 522 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-3-58 19
Application for plugging filed 12-4-58 19
Application for plugging approved 12-4-58 19
Plugging commenced 12-4-58 19
Plugging completed 12-4-58 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4231 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 13 3/8 | 30 | 0 |
| | | | | 8 5/8 | 250 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 240, plus & hulls, 20 sax cement. Filled hole to 40, plug, hulls, cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1958
CONSERVATION DIVISION
Wichita, Kansas
12-11-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox
522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 58
Helen Horine
Notary Public.

My commission expires June 4, 1959

PLUGGING
FILE SEC 1 T 30 R 9W
BOOK PAGE 3 LINE 23

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Zrubek
NW SE SW, Sec. 1-30-9W,
Kingman County, Kansas

Elevation 1581 KB
Set 30' of 13 3/8" w/50 sax
Set 250' of 8 5/8" w/175 sax
D & A

Commenced: 11-21-58
Completed: 12-2-58
Contractor: Rupp-Ferguson Oil Co.

Figures Indicate Bottom of Formation

30 sand & red bed
600 red bed
900 shale & shells
1085 salt & shale
1120 Anhydrite & shale
1260 shale & shells w/lime
1470 lime & shale
1645 lime
1793 lime, shale & sand
2220 shale & lime
2459 shale, lime streaks
2480 lime
2780 shale
3502 lime & shale
3834 lime
3912 lime, black shale
4094 lime
4139 lime & shale
4231 Miss. lime
T.D.

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

I, L. W. Knox, Partner in Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Zrubek well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 8th day of December, 1958.

Helen Horne
Notary Public

My Commission Expires June 4, 1959.

PLUGGING
FILE SEC. 1-30-9W
BOOK PAGE 3 LINE 23

DEC 11 1958
CONSULTATION DIVISION
Mont., Kansas