


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 30 Twp. 24 Rge. 13 (E) W(W)  
Location as "NE/CNW/SW" or footage from lines SW NE SE  
Lease Owner Arnell Company  
Lease Name H. Toland Well No. 1  
Office Address 101 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 22 19 57  
Application for plugging filed February 22 19 57  
Application for plugging approved February 22 19 57  
Plugging commenced February 22 19 57  
Plugging completed February 22 19 57  
Reason for abandonment of well or producing formation no oil in commercial quantities found.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4215 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	232'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 220'. Set Plug #1 at 220' with 20 sacks cement, 1/3 sack Hulls. Filled hole with extra heavy rotary mud from Plug #1 to 20'. Set Plug #2 with 5 sacks cement, 1/3 sack Hulls.

2-26-57

RECEIVED  
CORPORATION COMMISSION

FEB 26 1957

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Prime Drilling Company  
Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R R McNicol  
814-16 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February, 19 57

My commission expires Sept. 30, 1959

Darlene May  
Darlene May Notary Public.

PLUGGING  
FILE SEC 30 T 24 R 13W  
BOOK PAGE 143 LINE 22

ROTARY DRILLING LOG

OPERATOR: Artnell Company  
 H. Toland No. 1  
 SW NE SE Sec. 30-24-13  
 Stafford County, Kansas

CONTRACTOR: Prime Drilling Company  
 COMM: 2/7/57  
 COMP: 2/22/57

Remarks: Set 8-5/8" surface casing  
 at 232' cemented with 200 sacks  
 Pozmix, 2% C.C.

Formations:

Sand	74'
Shale	232'
Red Beds & Shale	670'
Shale & Shells	1515'
Shale	1830'
Lime	2610'
Lime & Shale	3125'
Lime	3539'
Lime & Shale	3645'
Lime	3928'
Shale & Lime	3969'
Lime	4032'
Lime & Chert	4120'
Lime, Chert & Shale	4159'
Shale & Lime	4215'
Rotary Total Depth (D&A)	4215'

We certify the above log is true  
 and correct to the best of our  
 knowledge and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*  
 R. R. McNicol

RECEIVED  
 OIL CORPORATION COMMISSION

FEB 26 1957

CONSULTATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE - SEC 30 T 24 R 13 W  
 BOOK PAGE 143 LINE 22