

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,656-0000

LEASE NAME Harter #1-30

WELL NUMBER NE SE SW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 30 TWP. 24s RGE. 13w (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 4/18/85

Plugging Completed 4/24/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947, Pratt, Ks. 67124

PHONE#(316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4275'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	300'	none
				4 1/2"	4253'	2029'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 1 sacks hulls, & 50 sacks cement, pushed plug to 3000'. Shot pipe at 3000', 2800', 2500', 2300', 2100', & 2029'. Pulled 48 joints of pipe.

Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 2% gel 3% c.c. Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. 5-1-85

R. Darrell Kelso

(Employee of Operator) or Notary Public

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well CONSERVATION DIVISION the same are true and correct, so help me God. Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1985

Irene Hoover
Notary Public

My Commission Expires:

