


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County. Sec. 30 Twp. 24 Rge. 13 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW NWNE  
Lease Owner Indian Wells Oil Co.  
Lease Name Copeland A#1 Well No.  
Office Address Lyons, Kansas 67554  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 8/13/80 19  
Plugging completed 8/20/80 19  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation Depth to top Bottom Total Depth of Well 4248'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	200	none
				4 1/2"	4010	2141'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped bottom with 35 sacks cement, pushed plug to 3700'. Shot pipe at 2894', 2762', 2600', 2500', 2411', 2308', 2214', 2114', pulled 65 joints. Pumped 8 sacks hulls, 25 sacks gel, 100 sacks 50-50 pos, 4% gel and 3% cc.

PLUGGING COMPLETE.

STATE CORPORATION COMMISSION  
RECEIVED 9-2-80  
SEP - 2 1980  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 80

My commission expires



Margaret Melcher  
Notary Public.

15-185-00964-0001

Indian Wells Oil Co.

30-24-13W

AYLWARD DRILLING

#1 COPELAND 'A'

NW NW NE

Contr. AYLWARD DRLG

STAFFORD

County

E. 1939 RB Comm.

Comp. 12-30-60

IP 3,688,000 CFG

Tops	Depth	Datum
LANS	3632	-1693
CONG	3927	-1988
VID	4017	-2078
SIMP	4148	-2209
ARB	4199	-2260
TD	4248	-2309

Casing

8" 200

OWNO: ORIG COMP AS

D & A 5-21-54 BY

UNITED DRLG CO.

DST 3757-3804/1 HR, 20' M

DST 4146-67/1 HR, 62' O & GCM

DST 4159-80/1 HR, 30' OC SW

NEW INFORMATION

4" 4009: PERF 18/3928-34: ACID 500:

FRAC: 3,688,000 CFG

HARTER POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1980  
CONSERVATION DIVISION  
Wichita, Kansas