

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 32 Twp. 24 Rge. (E) 13 (W)

Location as "NE/CNW/4SW/4" or footage from lines NE NE NE

Lease Owner Hinkle Oil Company

Lease Name Copeland Well No. 1

Office Address 914 Union Natl Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed August 31, 1949 19

Application for plugging approved August 31, 1949 19

Plugging commenced August 31, 1949 19

Plugging completed Sept 8, 1949 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. Stough

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5" OD	4210	2726
				8 5/8	260	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole to 3720'. Ran 5 sacks of cement.

Mudded hole to 260' of top. Ran 20 sacks of cement.

Mudded hole to 20' of top. Run 10 sacks of cement.

Well Completed

9-15-49

RECEIVED

Conservation Div.

SEP 15 1949

(If additional description is necessary, use BACK of this sheet)

STATE CORPORATION COMMISSION

Correspondence regarding this well should be addressed to Hinkle Oil Company

Address 914 Union Natl Bank Bldg, Wichita, Kansas

Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. B. Hinkle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Hinkle


914 Union National Bldg. (Address)

SUBSCRIBED AND SWORN to before me this 14 day of September, 19 49.

Muriel A. Upton Notary Public.

My commission expires Jan. 17, 1950

22-5133-s 9-49-10M



*Bank*

Casing record.  
11 3/4" 260'  
5" 5210'

Copeland No. 1. NE NE NE 32-24-13 Stafford Co. Kansas.  
Owner: Hinkle Oil Company, et al.  
Contractor: J. B. Hinkle.  
Commenced 10-16-48 Completed. Nov. 3, 1948.  
Elevation 1938.

0	40	sand
40	104	sand and gravel
104	220	shale and shells
220	300	red bed
300	1000	red shale and shells
1100	1200	red bed
1200	1300	shale and shells
1300	1605	lime and shale
1605	1815	shale and shells
1815	1925	lime and shale
1925	2060	lime
2060	2315	lime and shale
2315	2405	shale and shells
2405	2670	lime and shale
2670	2810	shale and shells
2810	3635	lime and shale
3635	3954	lime
3954	4002	lime and shale
4002	4012	lime
4012	4043	lime and chert
4043	4057	lime
4057	4070	lime and chert
4070	4210	lime
4210	4255	lime and shale
4255	4210	lime and shale Artuckle

Tops. K.O.	3589	
Hornton	3670	base 3925
Viola	3972	-2034
Sigson	4122	
Artuckle	4275	-2227
3 well show oil	4282	

**RECEIVED**  
Conservation Div.  
SEP 15 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

State of Kansas )  
County of Sedgewick. ) ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well. Further affidavit omitted.

J. B. Hinkle

Subscribed to and sworn to before me this 13th day of November, 1948.

Muriel A. Upton

My commission expires 1-17-50

**PLUGGING**  
DATE SEP 30 1949  
BOOK PAGE 13 LINE 29