

## WELL PLUGGING RECORD

Stafford County. Sec. 30 Twp. 24S Rge. 13/E/ (W)  
Location as "NE/CNW¼SW¼" or footage from lines SE NW SW  
Lease Owner L.B. Stableford  
Lease Name N. Harter Well No. 1  
Office Address 612 Union National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed July 26 19 50  
Application for plugging filed July 26 19 50  
Application for plugging approved July 26 19 50  
Plugging commenced July 26 19 50  
Plugging completed July 26 19 50  
Reason for abandonment of well or producing formation No shows of oil  
of commercial value  
If a producing well is abandoned, date of last production ----- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

### CASING RECORD

[illegible]

Withdrew drill pipe to 1900' and circulated heavy rotary mud for 30 minutes. Bridged hole with wooden plug and 5' chat @ 240'. Spotted 15 sax of cement through drill pipe from 190' to 235'. Capped surface pipe with 5 sax cement.

RECEIVED  
JAN 10 1964  
U.S. DEPT. OF JUSTICE

7-29-50

JUL 29 1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Clinton Engstrom, SAs  
Address 612 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Clinton Engstrand (agent, ~~employee of owner~~ or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
 described well as filed and that the same are true and correct. So help me God.

(Signature)

612 Union Nat'l. Bk. Bg. Wichita, Kans.  
(Address)

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of July, 1950

My commission expires June 5, 1954

23-3278-S

4-50-10M

**PLUGGING**  
 FROM SEC 30 T 24 R 13  
 BOOK PAGE 18 LINE 18

15.185.19035.0000

L.B. STABLEFORD  
N. HARTER "A" #1

SE NW SW Sec. 30 Twp. 24S Rge. 13W  
Stafford County, Kansas

Total Depth: 3798'  
Comm: 7/13/50  
Comp: 7/26/50

Casing

Cement

8 5/8" Set @ 242'

175 Sacks

Formation	Depth
Sand	0 - 165
Shale & shells	165 - 243
Red bed	243 - 650
Red bed & sand	650 - 830
Anhydrite	830 - 860
Shale & shells	860 - 1760
Lime & shale	1760 - 1960
Lime	1960 - 2015
Lime & shale	2015 - 2175
Lime	2175 - 2205
Lime & shale	2205 - 2875
Lime	2875 - 2935
Lime & shale	2935 - 3145
Lime	3145 - 3550
Lime & shale	3550 - 3620
Lime	3620 - 3798

STATE OF KANSAS)

) SS

SEDGWICK COUNTY)


I hereby certify that the above information is true and correct to the best of my knowledge.

*[Signature]*

Subscribed and sworn to before me this 4th day of August, 1950.

*[Signature]*

My commission expires: 6-5-54



**PLUGGING**  
FILE SEC 30 T 24 R 13W  
BOOK PAGE 18 LINE 18

SEP 9 X 1950

STATION  
COMMUNICATION  
KANSAS