

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Trego SEC. 28 TWP. 11S RGE. 22 E/W  
Location as in quarters or footage from lines:  
SW NE NE


Lease Owner Kansas Oil Corporation  
 Lease Name Honas "A" Well No. 4  
 Office Address 250 N. Rock Rd. - Suite 300  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed April 11, 1981  
 Application for plugging filed Verbally 4-11-81  
 Plugging commenced 4-11-81  
 Plugging completed 4-11-81  
 Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Locate Well  
correctly on above  
Section Platt.

Name of Conservation Agent who supervised plugging of this well Marion Schmidt (Both notified)  
Gil Balthazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3935'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	318'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

TD 3935'  
Set 1st plug at 900' with 60 sacks  
Set 2nd plug at 330' with 30 sacks  
Set 3rd plug at 40' solid bridge with 10 sacks  
Mousehole 5 sacks  
Rathole 5 sacks  
Cemented with 50/50 pozmix; 6% gel  
Plug was down at 5:35 p.m. April 11, 1981

4-22-81


RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1981  
WICHITA, KANSAS  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Services (Hays, Ks.) for KANDRICK CO, Ltd.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
C. K. Morrison (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) CK Morrison  
Bldg. 1- Ste. 207, 555 North Woodlawn  
Wichita, Ks. 67208 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 81



Paula R. Murrell  
Notary Public.  
My Commission expires March 16, 1985

APRIL 21, 1981

CONTRACTOR'S WELL LOG

OPERATOR: Kansas Oil Corporation  
 CONTRACTOR: Spartan Drilling Corporation  
 WELL NAME: #4 Honas "A"  
 LOCATION: SW NE NE Sec. 28-T11S-R22W Trego County, Ks.  
 API NO.: 15-195-20,779  
 COMMENCED: April 2, 1981  
 COMPLETED: April 11, 1981

Drilled 326' of 12 1/4" hole. Set 318" of new 8-5/8" 20# casing with 190 sacks of common cement, 2% gel 3% Ca Cl. Cement did circulate to surface. Plug was down at 9:00 p.m., April 2, 1981.

FORMATION	TOP'	BOTTOM'
Shale and Sand	0	318
Shale	318	1738
Lime and Shale	1738	2116
Shale and Sand	2116	2435
Shale and Lime	2435	2768
Shale	2768	3127
Shale and Lime	3127	3560
Lime	3560	3595
Lime and Shale	3595	3935

RTD 3935'. Set 1st plug at 900' with 60 sacks, set 2nd plug at 330' with 30 sacks, set 3rd plug at 40' solid bridge with 10 sacks, mousehole with 5 sacks, rathole with 5 sacks. Cemented with 50/50 pozmix, 6% gel. Plug was down at 5:35 p.m. April 11, 1981.


STATE OF KANSAS, COUNTY OF SEDGWICK, SS:

I, C. K. Morrison, of KANDRILCO, Ltd., do hereby state that the above is a true and correct copy of the Driller's Log for the #4 Honas "A" located in Trego County, Kansas.

KANDRILCO, Ltd.

*C. K. Morrison*  
 C. K. Morrison, President

RECEIVED  
 STATE CONSERVATION COMMISSION  
 APR 22 1981  
 CONSERVATION DIVISION  
 Kansas



Subscribed and sworn to before me, a Notary Public, in and for the State aforesaid, as of this 21st day of April, 1981.

*Paula R. Murrell*  
 Paula R. Murrell - Notary Public

My Commission expires:  
*March 16, 1985*