

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20,794-0000

LEASE NAME Meyer

WELL NUMBER 1

990 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 25 TWP. 24 RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3-27-03

Plugging Completed 3-28-03

RECEIVED
APR 09 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L.D. HALE

ADDRESS 1500 Timberlake Rd. Wichita, Ks. 67230

PHONE# (316) 733-5590 OPERATORS LICENSE NO. 3910

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4192'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	469'	None
				5-1/2"	4189'	1810'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet each side. Plugged off bottom with sand to 2050' and 5 sacks cement. Shot pipe @1810', pulled up to 850', pumped 10 sacks gel and 50 sacks cement, pulled up to 500', pumped 50 sacks cement, pulled up to 40' and topped off with 30 sacks cement, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: L.D. Hale

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 7th day of April, 2003

[Signature]
Notary Public

My Commission Expires:



Form 9
Revised 05-