

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
5 S. Market, Room 2078  
Topeka, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-185-20,732-00-00

LEASE NAME Koelsch

WELL NUMBER 2-A

413 Ft. from S Section Line

3151 Ft. from E Section Line

SEC. 25 TWP. 24S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-4-02

Plugging Completed 9-6-02

LEASE OPERATOR REGINALD D. FISHER

ADDRESS 110 N. Exchange St. John, Kansas 67576

PHONE (620) 549-6528 OPERATORS LICENSE NO. 3493

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

A plugging proposal was approved on \_\_\_\_\_ (date)

Scott Alberg (KCC District Agent's Name)

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2199'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	287'	None
				4-1/2"	2198'	1420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. Plugged off bottom with sand to 1700' and 4 sacks cement. Shot pipe @1420', pulled up to 850', pumped 10 sacks gel, 50 sacks cement w/100# hulls, pulled up to 325', pumped 50 sacks cement w/100# hulls, pulled up to 40' and circulated 30 sacks cement to surface 60/40 pos 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Reginald D. Fisher

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed thereon are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of September, 2002

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



OR