


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 25 Twp. 24 Rge. 14 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SEC SW
Lease Owner T.L. Nutt
Lease Name Koelsch Well No. 4
Office Address Box 407, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4/15/53 19
Application for plugging filed February 2, 1959 19
Application for plugging approved February 3, 1959 19
Plugging commenced February 10, 1959 19
Plugging completed February 12, 1959 19
Reason for abandonment of well or producing formation Non-commercial



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production January 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Arbuckle Depth to top 4171 Bottom 4172 Total Depth of Well 4172 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249'	None
				5 1/2"	4171'	2543'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4172' - 4130' - Sand
4130' - 4100' - 5 sacks cement
4100' - 0' - Pumped 15 sacks mud & 70 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T.L. Nutt (employee or owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]
Box 407, Ellinwood, Ks (Address)

SUBSCRIBED AND SWORN TO before me this 27 day of March, 1959

My commission expires Feb 25, 1963
Eusey J. Miller Notary Public.

PLUGGING
FILE SEC. 25 T. 24 R. 14W
BOOK PAGE 13 LINE 42


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company: HILTON DRILLING CO., INC.,
Farm: Koelsch No. 4

SEC. 25 T. 24 R. 11W
S10 SW

Total Depth. 4172
Comm. 3-31-53 Comp. 4-15-53
Shot or Treated.
Contractor.
Issued. 6-20-53

County Sedgwick
KANSAS



Dev. on 1111
Production. 25,000, no wtr.

CASING:

8 5/8 419' w/ 200 cc cement
5 1/2 4171' w/ 150 cc cement

Figure 1. Waste Bottom of Formations.

sand & gravel	110
shale & shells	130
red rock	150
red rock, shale & shells	170
anhydrite	195
shale & shells	1500
broken lime & shale	1420
lime	2015
lime & shale	2145
broken lime & shale	2540
lime & shale	2605
lime	2750
lime & shale	3270
lime	3310
lime & shale	3378
lime	3567
lime & shale	3717
lime	3854
lime & shale	4000
lime & chert	4022
lime	4116
shale, sand & lime	4155
shale	4169
lime	4172
Total Depth	

TOPS:	
Anhydrite	130
Heebner	3138
Leavenworth lime	3444
Snyderville shale	3449
Toronto lime	3451
Douglas shale	3476
Brown lime	3577
Lansing FC	3807
Kinderhook shale	3812
Viola	3796
Simpson shale	4131
Simpson sand	4139
Arbuckle	4172

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1962

CONSERVATION DIVISION
Wichita, Kansas