

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County. Sec. 25 Twp. 24 Rge. 14 ~~W~~ W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW SW

Lease Owner Hilton Drilling Company, Inc.

Lease Name Koelsch Well No. 3

Office Address 2421 Tenth Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed January 20 1953

Application for plugging filed January 20 1953

Application for plugging approved January 20 1953

Plugging commenced January 20 1953

Plugging completed January 20 1953

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	250	8 5/8	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud from 4263 T.D. to 240'. Plug set @ 240 (1 bucket hulls below plug). Hole filled with 20 sacks cement and heavy rotary mud from 240' to 35'. Plug set @ 35' (1 bucket hulls below plug). Hole filled with 10 sacks cement from 35' to surface.

RECEIVED
STATE CORPORATION COMMISSION

JAN 22 1953

1-22-53

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hilton Drilling Company, Inc.
Address P. O. Box 108, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Henry Peacock (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HILTON DRILLING COMPANY, INC.

(Signature) Henry Peacock Secretary

January 21, 1953 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of January, 1953.

Margaret Whitson
Notary Public.

My commission expires April 4, 1956

PLUGGING
FILE SEC 25 T 24 R 14 W
BOOK PAGE 74 LINE 19

D R I L L E R ' S L O G

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: NE SW SW 25-24-14
 Stafford County Kans.
 CONTRACTOR: HILTON DRILLING COMPANY, INC. ELEVATION: 1947 DF
 FARM NAME: KOELSCH NO. 3
 COMMENCED: 1-5-53
 COMPLETED: 1-20-53
 SURFACE: Pipe set 12-29-52 by Rosencrantz-Bemis Equipment Co.
 Casing Used: 8 5/8" @ 250' w/150 sx

Red Bed, shale and shells	615
Red Bed	835
Anhydrite	860
Shale and Shells	1535
Shale and Lime	1700
Broken Lime	1805
Lime	2415
Lime and Shale	2960
Broken Lime	3060
Lime and Shale	3145
Lime	3531
Shale and Lime	3648
Lime	3910
Lime and Shale	4025
Conglomerate	4066
Viola	4069
Lime, Shale and Chert	4113
Lime chert	4133
Viola	4155
Lime chert	4171
Viola lime chert	4197
Lime and Shale	4229
Shale	4252
Arbuckle	4263
Total Depth	4263

TOPS:

Heebner	3449
Kansas City	3640
Viola	4049
Simpson Sd	4199
Arbuckle	4239

STATE OF KANSAS)
 COUNTY OF BARTON) SS.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 22 1953

CONSERVATION DIVISION
 Wichita, Kansas

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

PLUGGING
 FILE SEC 257-24-14W
 BOOK PAGE 74 LINE 19

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 21st day of January, 1953.

My commission expires 4-4-56

Margaret Whitman
 Notary Public