


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 25 Twp. 24S Rge. 14W (RXX) (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner HILTON DRILLING COMPANY, INC.
Lease Name KOELSCH Well No. 2
Office Address P.O. Box 108, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed NOVEMBER 23, 19 48
Application for plugging filed NOVEMBER 19, 19 56
Application for plugging approved NOVEMBER 20, 19 56
Plugging commenced NOVEMBER 26, 19 56
Plugging completed NOVEMBER 29, 19 56
Reason for abandonment of well or producing formation STOPPED PRODUCING OIL

If a producing well is abandoned, date of last production NOVEMBER 1, 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. M. BRUNDEGE
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4215 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	NONE
				5-1/2"	4215'	2926'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK WITH SAND TO 4170' AND DUMPED 5 SACKS OF CEMENT.
PLUGGED WITH 25 SACKS OF GEL MUD AND 90 SACKS OF CEMENT AND 3% CHLORIDE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DAN H. COOK, VICE PRESIDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dan H. Cook*
GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of NOVEMBER, 19 56.

Mildred Hobbie
Notary Public.

My commission expires _____

PLUGGING
FILE SEC 25 T. 24 R. 14W
BOOK PAGE 117 LINE 43

RECEIVED
STATE CORPORATION COMMISSION
MILDRED HOBBS
MARCH 6, 1958
DEC 6 - 1956 12-6-56
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: SE NE SW
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Sec. 25-24-14
 FARM NAME: KOELSCH NO. 2 Stafford County,
 Kansas
 COMMENCED: 11-2-52 ELEVATION: 1945 KB
 COMPLETED: 11-17-52

Casing Used: 8-5/8 set at 249' w/200 sacks
 5-1/2 set at 4215' w/100 sacks

Sand	41
Sand and Gravel	120
Sand, Shale and Shells	225
Red Bed	830
Anhydrite	855
Shale and Shells	1320
Salt, Shale and Shells	1425
Shale and Lime	1765
Lime	2210
Lime and Shale	2325
Lime	2460
Lime and Shale	3075
Lime	3165
Lime and Shale	3265
Lime	3400
Lime and Shale	3636
Lime	3948
Lime and Chert	3980
Conglomerate	4023
Lime, Shale and Chert	4067
Chert and Lime	4128
Chert, Lime and Shale	4153
Lime and Shale	4157
Simpson	4196
Shale and Lime	4215.5
Total Depth	4215.5

TOPS:

Heehner	3449	-1504
Toronto	3471	-1526
Brown Lime	3586	-1641
Lansing	3615	-1670
Viola	4015	-2070
Simpson Shale	4171	-2226
Simpson Sand	4181	-2236
Arbuckle	4214	-2269

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

RECEIVED
 NOV 20 1952
 PLUGGERS CONSERVATION DIVISION
 STATE CORPORATION COMMISSION
 FILE NO. 25-24-14-114
 BOOK PAGE 117 LINE 43
 WICHITA, KANSAS

HILTON DRILLING COMPANY, INC.

Henry Peacock, Secretary

Subscribed and sworn to before me this 18th day of November, 1952.

Margaret Whitman
 Notary Public