


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County, Sec. 25 Twp. 24S Rge. 14 ~~(E)~~ ^{XX} (W)
 Location as "NE/CNW/SW" or footage from lines NE SE SW
 Lease Owner Hilton Drilling Company, Inc.
 Lease Name Koelsch Well No. 1
 Office Address P. O. Box 108, Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed October 22, 19 52
 Application for plugging filed November 19, 19 56
 Application for plugging approved November 20, 19 56
 Plugging commenced November 20, 19 56
 Plugging completed November 24, 19 56
 Reason for abandonment of well or producing formation Well stopped producing oil
 If a producing well is abandoned, date of last production November 1, 19 56
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundage
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4191 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	249'	8-5/8"	249'	None
			4189'	5-1/2"	4189'	2805.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 4140', dumped in 5 sacks cement.
Put in 25 sacks gel mud and 90 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1956
CONSERVATION DIVISION
Wichita, Kansas

11-30-56

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Ace Pipe Pulling Company
 Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Dan H. Cook, Vice-President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 19 56
[Signature]
 Notary Public.

PLUGGING
 FILE SEC 25 T. 24 R. 14W
 BOOK PAGE 117 LINE 42

D R I L L I N G L O G

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: NE 22 SW
 Sec. 25-24-14,
 Stafford Count
 Kansas
 CONTRACTOR: HILTON DRILLING COMPANY, INC.
 WELL NAME: NOELSON NO. 1 ELEVATION: 1943 DF
 COMMENCED: 10-1-52
 COMPLETED: 10-16-52

Casing Used: 6 5/8 set at 249' w/250 sacks
 5 1/2 set at 4187' w/175 sacks

Sand	41
Sand and gravel	165
Shale and shells	160
Sand	210
Shale and Red Bed	235
Red Bed	330
Anhydrite	355
Shale and shells	1200
Salt, shale, and shells	1425
Shale and lime	1715
Lime broken	1735
Lime	2030
Lime and shale	3185
Lime	3403
Lime and shale	3624
Lime	3958
Lime and shale	4005
Viola lime and chert	4041
Viola, chert, and shale	4067
Viola lime and chert	4110
Viola	4135
Simpson	4140
Simpson and Arbuckle Lime	4191
Total Depth	4191

TOPS:

Lansing	3606	-1661
Viola	4000	-2055
Simpson Shale	4115	-2200
Simpson Sand	4150	-2211
Arbuckle	4187	-2242

STATE OF KANSAS }
 COUNTY OF BARTON } SE

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

RECEIVED
 PLUGGING DATE CORPORATION COMMISSION
 FILE SEC 25 T 24 R 14W
 BOOK PAGE 117 LINE 4 2 NOV 20 1956
 CONSERVATION DIVISION
 Wichita, Kansas

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 20th day of October, 1952.

Margaret Whitmore
 Notary Public