


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 West Market
Wichita, Kansas

Stafford County. Sec. 25 Twp. 24 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Morgenstern Oil Operations
Lease Name Abbott Well No. 4
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/ 1/67 19
Plugging completed 9/ 6/67 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation Depth to top Bottom Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	838'	none
				5-1/2"	3899'	3182'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3900' and ran sand to 3850'. Ran 5 sacks of cement. Loaded hole with water, shot pipe at 3185', worked pipe. Spotted 40 barrels of oil, worked pipe loose. Mudded hole to 415' and set 10' rock bridge. Ran 25 sacks of cement. Mudded hole to 40' and set 10' rock bridge and ran 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1967

9-21-67
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss:
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of Sept. 19 67

My commission expires February 15, 1971

Margaret Melcher
Notary Public.

DRILLERS' LOG

Company: Halmerich and Payne, Inc.

NE NW NW
Sec. 25, Twp. 24S, Rge. 14W,

Farm Name: Abbott Well No. 4

County: Stafford,
Kansas

Total Depth: 3900'

Elevation:

Comm: 9-16-55 Comp: 9-27-55

Contractor: Glenn W. Peal

Production:

Casings: 8 5/8" 838' con.
3 1/2" 3599' con.

Figures below indicate bottoms of formations:

Sand, shale, red bed	0 -	400
Shale and shells		825
Anhydrite		865
Shale and shells		1855
Lime		2000
Lime and shale		2320
Shale and lime streaks		2440
Lime and shale		2785
Shale and lime streaks		2900
Lime and shale		3025
Lime		3900
Total Depth		3900

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEAL

BY: *Glenn W. Peal*

SUBSCRIBED AND SWORN to before me this 7th day of October, 1955.

My commission expires: June 4, 1959

Marion M. Herbst
Notary Public

NOTARY PUBLIC
AUG 4 1967
WICHITA, KANSAS