


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 25 Twp. 24 Rge. 14 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Morgenstern Oil Operations
Lease Name Abbot Well No. #3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved 19__
Plugging commenced 8/28/67 19__
Plugging completed 9/ 1/67 19__
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elvin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	848	none
				5 1/2	3790	3028'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3900' and ran sand to 3750', ran 5 sacks of cement.
Shot pipe at 3309', spotted oil. Shot pipe at 3144', 3011', worked pipe loose. Mudded hole to 500', set 10' rock bridge and ran 25 sacks of cement. Mudded hole to 40', set 10' rock bridge and ran 10 sacks of cement. Tallied pipe.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1967

CONSERVATION DIVISION
Wichita, Kansas

9-21-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of Sept., 19 67

Margaret Melcher

Notary Public.

My commission expires Feb. 15., 1971

DRILLER'S LOG

Company: Helmerich & Payne, Inc.

SE NW NW
Sec. 25, Twp. 24S, Rge. 14W

Farm: Abbott Well No. 3
Total Depth: 3900'

County: Stafford,
Kansas

Comm: 3-4-53 Comp: 3-18-53
Contractor: Peel Brothers, Inc.

Elevation:

Casing:
8 5/8" 848' cem.
5 1/2" 3790' cem.

Production:

Figures below indicate bottom of formations

Sand	0 -	70
Sand & Shale		385
Shale & Red Bed		735
Red Bed		844
Anhydrite		877
Shale & Shells		1700
Shale with Lime streaks		1745
Shale, Salt & Shells		1800
Lime		2010
Shale & Lime streaks		2130
Shale & Lime		2370
Lime		2405
Lime & Shale		3340
Lime		3445
Lime & Shale		3480
Lime		3570
Lime & Shale		3685
Lime		3900
Total Depth		3900

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1967
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.

BY: Mendell L. Peel

SUBSCRIBED AND SWORN to before me this 19th day of March, 1953.

My commission expires January 9, 1957 Haris B. Welch
Notary Public