


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-185-12988-0000
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 25 Twp. 24S Rge. (E) 14(W)
Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner Shell Oil Company
Lease Name L. ABBOTT Well No. 1
Office Address 1845 Sherman Street, Denver 3, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 17 1953
Application for plugging filed July 21 1960
Application for plugging approved July 26 1960
Plugging commenced August 5 1960
Plugging completed August 11 1960
Reason for abandonment of well or producing formation Oil Depleted

If a producing well is abandoned, date of last production July 17 1960
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Arbuckle Depth to top 4174 Bottom - Total Depth of Well 4186 Feet
Show depth and thickness of all water, oil and gas formations. PB 4118

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Ind. cap.	4175	4186	8 5/8"	832'	None
	3548 BO, no water, 24 hrs.			5 1/2"	4175'	3109'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/ sand to 3710. Dumped 5
sax cement to 3670. Filled hole with mud to
250, set rock bridge to 240 & dumped 20 sax
cement to 178. Mudded hole to 40, set rock
bridge to 30 & capped with 10 sax cement to base
of cellar.

9-8-60

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling Company
Address P. O. Box 221, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
L. W. Elderkin (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Elderkin
L. W. Elderkin, Div. Prod. Supt.
1845 Sherman Street, Denver 3, Colorado (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1960

My commission expires September 3, 1963

Donald M. DeMuth
Donald M. DeMuth Notary Public.

SHELL-L. ABBOTT No. 1
SE SW NE Section 25-24S-14W
Koelsch, S. E. Field
Stafford County, Kansas

Casing Record

8 5/8" cem 832 with 555 sax
5 1/2" cem 4175 with 175 sax; perf 3721-3724

0 - 180 sand
215 sand & shale
280 shale & red bed
330 red bed
570 red bed & shale
640 shale & sand
740 shale & shells
825 red bed & shells
835 anhydrite
1370 red bed & shale
1700 salt & shale
1775 shale & shells
2115 lime & shale
2150 shale & lime
2250 lime & shale
2415 shale & lime
2515 lime & shale
2720 shale & lime
2878 lime & shale
3025 shale & lime
3190 lime & shale
3215 shale & lime
3300 lime & shale
3429 lime
Top Heebner 3429
3437 shale
3484 lime, streaks shale
3510 shale
3595 shale, calcareous
Top Lansing-Kansas City 3595
3692 lime
3714 lime, shale streaks, chert
3727 lime
3738 lime, shale streaks
3745 shale
3760 lime, shale streaks
3765 lime
3776 lime, shale streaks
3790 lime
3827 lime, shale streaks
3844 lime
3854 shale
3864 lime
3880 shale
3908 lime, shale streaks
3920 shale, lime streaks
3960 lime, chert, shale streaks
3976 shale, calc.

3982 shale, calcareous
4000 chert, shale streaks
Top Viola 4000
4030 chert w/ lime
4050 lime, cherty & chert
4133 chert, lime, shale streaks
Top Simpson 4133
4143 shale, trace sand, qtz grains
4174 shale, sand streaks, qtzitic
Top Arbuckle 4174
4186 dolomite T.D.
4118 P.B.

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1960

CONSERVATION DIVISION
Wichita, Kansas