


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 25 Twp. 24 Rge. 14 (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW NW SE NE
Lease Owner United Drilling, Inc.
Lease Name Abbott Well No. 1
Office Address 814 Maple St., Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed February 26 19 54
Application for plugging filed February 26 19 54
Application for plugging approved _____ 19 _____
Plugging commenced February 26 19 54
Plugging completed February 26 19 54
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4255 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged from 4255' to 270' with rotary mud; from 270' to 170' with 50 sacks of cement; from 170' to 40' with rotary mud; from 40' to 0' with 10 sacks of cement. Job completed at 4:00 P.M. February 26, 1954

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Russell, ss.
Clyde G. Kissinger (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
814 Maple St., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 54

My commission expires 10-30-57

Marlene Zook
Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
24-7988-S 3-53-20M
3-31-54

PLUGGING
WELL SEC 25 TWP 24 R 14 W
BOOK PAGE 16 LINE 27

ABBOTT #1 WELL

Contractor: United Drilling, Inc.
 Operator: United Drilling, Inc.
 Commenced: February 8, 1954
 Completed: February 26, 1954

LOCATION: SW NW ^{NE} SE,
 Section 25--24S--14W,
 Stafford Co., Kansas
 Dry and Abandoned

Casing Record:

8 5/8" casing set 192 feet.

--WELL LOG--

65 feet	Sand and Clay
90 "	Shale
193 "	Shale
260 "	Shale, Sand and Red Bed
827 "	Anhydrite
850 "	Shale and Shells
1325 "	Salt and Shale
1462 "	Shale and Shells
1690 "	Shale
1825 "	Lime and Shale
2280 "	Lime and Shale
2510 "	Shale and Lime and Shells
2610 "	Shale and Shells
2755 "	Shale and Lime
2870 "	Shale, Lime and Shells
2930 "	Lime and Shale
3145 "	Lime
3290 "	Lime and Shale
3350 "	Lime
3430 "	Lime and Shale
3475 "	Lime
3525 "	Shale and Lime
3575 "	Shale
3592 "	Lime and Shale
3615 "	Lime
3758 "	Lime and Shale
3795 "	Lime
3911 "	Lime and Shale
3945 "	Shale, Lime and Chert
3985 "	Shale and Lime
4005 "	Shale, Lime and Chert
4045 "	Lime and Chert
4075 "	Shale and Cherty Lime
4095 "	Chert and Lime
4155 "	Lime, Chert and Shale
4195 "	Shale
4210 "	Shale and Lime
4230 "	Lime

4255 " Total Depth

RECEIVED
 CORPORATION COMMISSION

STATE OF KANSAS
 COUNTY OF RUSSELL
 MAR 3 1 1954
 SS:
 DIVISION

I hereby certify that the above and foregoing information is true and correct to the best of my knowledge.

PLUGGING
 FILE SEC 25 T 24 R 14W
 BOX PAGE 16 LINE 27

Clyde G. Kissinger
 Clyde G. Kissinger
 President of United Drilling, Inc.

SUBSCRIBED AND SWORN to before me, a Notary Public, this
 17th day of March, 1954.

My Commission Expires:
 10-30-57

Marlene Zook
 Notary Public