

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1964
11-24-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Company

Complete Address: 1015 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Griem Well No. # 1

Location SW NW SW Sec. 1 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4250

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sierra Petroleum Company

Address: 1015 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:30PM Day 22nd Month Nov. Year 1964

The Above well was plugged as follows:

238' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was
filled with drilling mud to 235', 1st cementing plug, bridged solid with
dry cement and hulls on fluid at 235', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 11/25/64
INV. NO. 211-4

Signed: Archie Elving
Well Plugging Supervisor