

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185-00964-0001 (of this well)

Operator's Full Name Indian Wells Oil Co.

Complete Address 620 S. Douglas, Lyons, Ks. 67554

Lease Name Copeland "A" Well No. 1

Location NW NW NE Sec. 30 Twp. 24 S Rge. 13 (E) (W) X

County Stafford Total Depth 4248

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12:15 Pm. Day 20 Month 8 Year 1980

The above well was plugged as follows:

200' 8 5/8" casing. 4 1/2" casing set at 4010' w/200 sax cement. Top
pref., at 3928'-Allied mixed & pumped 35 sax common cement in 4 1/2"
casing to 3700'-Pull 2114' casing-Allied mixed & pumped 8 sax hulls
25 sax gel-100 sax 50/50 posmix cement w/4% gel & 3% cc to top of
casing. Shut in w/0 pressure.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

INVOICED

STATE CORPORATION COMMISSION Signed: _____

Well Plugging Supervisor

DATE 8-26-80

AUG 25 1980

INV. NO. 2940W

CONSERVATION DIVISION
Wichita, Kansas