

15-185-00792-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE  
~~SE~~ - NE - NE

SEC. 30 TWP. 24 RGE. 13

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Copland

Operator Nickle Oil Co Address #914 N.W. Bldg - Wichita - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 4210 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 260 ft. Circulated with cement.  
5" casing at 4210 ft. Plugged back from  
bottom to 3920 ft. With Lane Wells Plug & chat.  
Dumped 3 sacks of cement at 3920 ft. Shot off &  
Pulled the 5" casing - Filled with mud to 260 ft.  
Set Rock Bridge & 20 sacks of cement at 260 ft.  
Mud to 25 ft. Plug & 10 sacks of cement at the surface

Edith Storch - 9-12-49  
District Conservation Agent

Date 9-8-49 Conservation Div.

**PLUGGING**  
WELL SEC 30 TWP 24 R 13  
BOOK PAGE 113 LINE 29

SEP 12 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

F