

KANSAS

*af*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Inc.

Complete Address Box 922 Great Bend, Ks

Lease Name Aitken Well No. 1

Location SE/SE/NW Sec. 30 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 4174

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. \_\_\_\_\_

Operation Completed: Hour 10:00 AM Day 8 Month 8 Year 1972

The above well was plugged as follows:

312 ft 8 5/8 surface pipe cemented with 225 sacks. 4168 ft 5 1/2 long

string cemented with 200 sacks. Top perf. 3671 ft. Push plug to

3650 ft, 5 sacks cement with bailer. Pulled 2300 ft 5 1/2. Pump 2 sacks

hulls, 15 sacks gel, 100 sacks cement to surface.

Pumped by Halliburton Cementing Co. Great Bend, Ks

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: B. Russell Bibeaux  
Well Plugging Supervisor

DATE 8-10-72

INV. NO. 6139-10