

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-NE-SW

SEC. 30 TWP. 24 RGE. 13W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Harter

Operator I. B. Stapleford Address 1003 annual stldg
Wichita Kansas

Field _____ County Stoddard

Total Depth 4247 Feet.

(Describe briefly the manner in which the well was plugged)

8 3/4" 240' 150 # Cement

5 1/2" 4207' 150 # Cement Plugged back.

I.W. Plug 3828' Top Repairs 3188

filled with gravel to 3670' run 5 #

Cement with dump failure pulled

5 1/2" casing pumped 15 # Jell Mud

and 75 # Cement Cement 240' to base

of cellar cement and mud pumped by Halperton
Cementing Co

Jim Forbes Pulling Contractor

RECEIVED 10-23-52
STATE CORPORATION COMMISSION

OCT 23 1952
CONSERVATION DIVISION District Conservation Agent
Wichita, Kansas Date 10-21-52

PLUGGING
FILE SEC 30 T 24 R 13W
PAGE 52 LINE 43