

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name Harter Well No. # 2

Location NW NE SW Sec. 30 Twp. 24 Rge. 13 (E) (W)

County Stafford Total Depth 4189

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 4:30PM Day 13th Month July Year 1964

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cemented with 175 sacks. 4181' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 3975'. Top perforation
3762'. Bottom of the hole was sanded to 3750', and cemented with 5 sacks.
Hole was flowing with water, and a squeeze job was necessary. 10 sacks
of Gel-Mud and 75 sacks of cement, with 2% Calcium Chloride, was pumped
into the surface pipe, through an 8 5/8" swage, to a pressure of 300 lbs.
A wiping plug was run between the Gel-Mud and the cement.
2994' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/64

INV. NO. 9492-W

Signed: Archie Elving
Well Plugging Supervisor