

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 71-1LOCATION SW-SW-SESEC. 25 TWP. 24 RGE. 14 WDry Hole _____ Abandoned Oil Well ☒ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease TRECELLASOperator SHELL OIL COMPANY Address Box 744 GT BEND, KANS.Field _____ County STAFFORDTotal Depth 4192 Feet.Plugging Contractor FORBES CASING PULLING CO.Plugging Contractor's License No. 49.Address GT BEND, KANSAS

(Describe Briefly the manner in which the well was plugged)

SADDLED BOTTOM 5'x TO 4170' W/5 SX CMT PLUG
SHOT PIPE 3292' BLEW IN-1150 LBS PRESSURE - PUMPED
218 BBLs HVY MUD TO KILL GAS - PULLED PIPE TO
800' - PUMPED 60 SX CMT - PULLED PIPE TO 318'
PUMPED HVY MUD AND 40 SX CMT - PULLED PIPE - SET
ROCK BRIDGE AT 35' - AND CAPPED TO BASE OF
CELLAR W/10 SX CMT

CEMENT PUMPED BY
HALLIBURTON

Frank Broadfork
District Conservation Agent

Date 1-15-58

PLUGGING

FILE SEC 25 T 24 R 14 W
BOOK PAGE 71 LINE 1