

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 4, 1967.

Operator's Full Name Morgenstern Oil Operations

Complete Address: P. O. Box 372, Wichita, Kansas 67201

Lease Name Abbott Well No. # 4

Location NE NW NW Sec. 25 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 3900'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 6th Month Sept. Year 1967

The Above well was plugged as follows:

838' of 8 5/8" surface pipe, cement circulated. 3899' of 5 1/2" long string,
cemented with 125 sacks. This is an open hole. Bottom of the hole was sanded
to 3850', and cemented with 5 sacks, through the dump bailer, with cement from
3850' to 3810'. 3185' of 5 1/2" long string was recovered from the hole. Hole
was filled with mud to 415', rock bridge from 415' to 405', and cemented with
25 sacks, with cement from 405' to 330'. Hole was filled mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 9/8/67
INV. NO. 6284-W