

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED

SEP 6 1967

9-6-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 4, 1967.

Operator's Full Name Morgenstern Oil Operations

Complete Address: P. O. Box 372, Wichita, Kansas 67201

Lease Name Abbott Well No. # 3

Location SE NW NW Sec. 25 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 1st Month September Year 1967

The Above well was plugged as follows:

848' of 8 5/8" surface pipe, cement circulated. 3790' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded
to 3750', and cemented with 5 sacks, through the dump bailer, with cement
from 3750' to 3710'. 3011' of 5 1/2" long string was recovered from the hole.
Hole was filled with mud to 500', rock bridge from 500' to 490', and cmented
with 25 sacks, with cement from 490' to 415'. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement
from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 9/6/67

INV. NO. 6265-W