

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 116-38LOCATION NW-NE-NWSEC. 25 TWP. 24 RGE. 14WDry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease AbbattOperator Helmerich & Payne, Inc. Address 821 Central Bldg.
Wichita, Kans.Field _____ County StaffordTotal Depth 3900 Feet.Plugging Contractor R & D Casing Pulling Co.Plugging Contractor's License No. 236Address Ellinwood, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" O 843' C.W.C. 5 1/2" O.D. Oil string
 set 3793' w/ 125 cc Cem. Cem. not drilled out

top perf. 3751' Sand to 3740 dump 5 cc Cem.

Shot off and pulled 5 1/2" casing. Filled

hole with heavy mud to 300' set rock bridge

and dumped 20 cc Cem. mud to 35' rock

bridge and 10 cc Cem. to base of cellar

RECEIVED
 STATE CORPORATION COMMISSION

MAY 19 1955

CONSERVATION DIVISION
 Wichita, Kansas

5-19-55

Warren G. Harner
 District Conservation Agent

Date May 17, 1955

PLUGGING
 FILE SEC 25 T 24 R 14W
 BOOK PAGE 116 LINE 38