

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado-Derby Building
Wichita, Kansas 67202

15-055-00001-0000 FORM CP-1
Rev. 6/4/84

Copy sent

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER October 24, 1952 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

OPERATOR Austin Brady OPERATORS LICENSE NO. 4186

ADDRESS P.O. Box 793, Garden City, Kansas 67846 PHONE # (316) 276-6928

SE (FARM) Sonderregger WELL NO. 1 WELL LOCATION NE/4-NE NE NE COUNTY Finney

21 TWP. 22 RGE. 31 S (E) or (W) TOTAL DEPTH 4968 PLUG BACK TD _____

Check One:

WELL GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 310 CEMENTED WITH 225 SACKS

CASING SIZE 5 1/2 SET AT 4968 CEMENTED WITH 225 SACKS

PERFORATED AT 4705-4726 & 4729-4748

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE 3880'

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 50 s/cs cement @ 3865 plug - mix & pump

50 s/cs cement plug @ 3150' - perforated @ 1150' pump 40 s/cs cement plug-pulled 240' of

casing spot 50 s/cs cement. Pulled casing - mix and pump 10 s/cs cement @ surface plug.

(If additional space is needed use back of form)

WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN January 24, 1986 - 1:00 P.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Austin Brady PHONE # (316) 276-6928

ADDRESS P.O. Box 793, Garden City, Kansas 67846

PLUGGING CONTRACTOR Bob Sargent LICENSE NO. N/A

ADDRESS Liberal, Kansas 67901 PHONE # (316) 624-7455

AGREEMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Austin Brady
(Operator or Agent)

DATE: _____

STATE CORPORATION COMMISSION

MAR 31 1986

CONSERVATION DIVISION

Copy sent