


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-009-30808-8000  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 31 Twp. 16 Rge. (E) 11 (W)  
Location as "NE/CNW/SE/SW" or footage from lines NE NE NW  
Lease Owner Harms Petroleum Company  
Lease Name Zorn Well No. 2  
Office Address Box 488, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed March 26 1968  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced April 25 1968  
Plugging completed May 4 1968  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3355 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	293'	8 5/8"	293'	none
		0	3347'	5 1/2"	3347'	2514.40

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand back to 2800' and dumped 5 sacks cement.

Squeezed well with 20 sacks gel and 80 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
E. L. Schonhoff (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. L. Schonhoff  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1968

My commission expires July 7, 1968

[Signature]  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- HARMS & KNIGHT DRILLING COMPANY  
Farm- Zorn No. 2 (Twin)

SEC. 31 T. 16 R. 17  
NE NE SW

Total Depth. 3355  
Comm. 2-20-52 Comp. 3-2-52  
Shot or Treated.  
Contractor. Harms & Knight Drig. Co.  
Issued. 12-20-52

County Barton KANSAS



Elevation. 1899

Production. 48 BOPD

CASING:

8 5/8" 293' cem. w/175 sx circ.  
5 1/2" 3347' cem. w/50 sx

Figures Indicate Bottom of Formations.

clay rock	60
shale & shells	90
sand	105
shale	230
sand	270
shale & shells	293
clay	420
sand	445
red bed	736
anhydrite	772
red bed	900
shale & shells	1250
salt	1350
shale & shells	1440
shale	1610
shale & lime	2105
shale	2340
shale & shells	2590
shale & lime	3030
lime	3175
shale & lime	3237
lime	3355
Total Depth	

Scout Tops:	
Hoebner	2958
Dodge	2973
Douglas	2987
Sand	3006
Brown Lime	3057
Lansing	3074
Congl.	3327

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

3074  
2958  
116