

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

9-23-80

SEP 23 1980

15-009-21901-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

WELL PLUGGING RECORD

Barton County. Sec. 31 Twp. 16 Rge. 11W E/W
Location as "NE/CNW1SW4" or footage from lines NW/NE/SW


Lease Owner Miles Petroleum and John R. Evans
Lease Name Zorn Well No. 2
Office Address 405 Fourth St., Claflin, KS 67525
Character of Well (Completed as Oil, Gas or Dry Hole) Oil

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced September 15 1980
Plugging completed September 19 1980
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3328'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258	None
				5-1/2"	3321'	2369.26'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 2950' and 5 sacks cement.
Shot pipe at 2520' and 2400'.
Pulled 57 joints 5-1/2" casing.
Squeezed well with 4 sacks hulls, 25 sacks gel, 1 sack hulls, 100 sacks 50/50 pozmix cement with 4% added gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold, Box 698, Great Bend,
(Address) KS 67530

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1980

Richard L. Shoen
Notary Public.

My commission expires September 27, 1981

WELL LOG

OPERATOR: John Roy Evans & Miles Petroleum

WELL NAME: # 2 Zorn LOCATION: SW/4 Sec.31-16S-11W

COUNTY: Barton STATE: Kansas

WELL COMMENCED: 4-21-80 WELL COMPLETED: 5-2-80

ELEVATION: 1883 GL TOTAL DEPTH: 3328'

PRODUCTION: RIG NO: 1

CASING - 8 5/8" 7 Jts. used tallied 253.95 set @ 258' Cemented with 165 sxs of Common Cement, 3% CC 2% Gel
5 1/2" 82 Jts. new 17# set @ 3322. Cemented with 175 sxs of 60/40 POZ Mix. 20 barrels of Salt Flush. Plug down 6:15AM

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING: 5-2-80.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	20	Top Soil & Post Rock		4-27-80 DST #1 @ 3000'
20	264	Sand & Shale		4-28-80 DST #2 @ 3104'
264	720	Sand-Shale & Redbed		5- 1-80 DST #3 @ 3327'
720	1140	Anhydrite		
1140	1502	Sand & Shale		
1502	3328	Lime & Shale		

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

BIG KAT, INC.

By *[Signature]*



SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 6th day of May, 1980.

Elfie A. Lacio

My Commission Expires: 4-4-1984

NOTARY PUBLIC
Elfie A. Lacio