

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-15079-0000

LEASE NAME B Vilenta

WELL NUMBER #6

 Ft. from S Section Line

 Ft. from E Section Line
 SW NE NE

SEC. TWP. RGE. (E) or (W) (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 8-8-88

Plugging Completed 8-18-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS P.O. Box 6
Great Bend, Kansas 67530

PHONE# (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3346'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	750'	none
				5-1/2"	3344'	2114'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 2900' and 5 sacks cement. Shot pipe @2520', 2416', 2330', 2211', 2114', pulled a total of 65 joints of 5-1/2" casing. Plugged surface with 500# hulls and 200 sacks 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss. /

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1988

Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

SEP - 8 1988 09-08-88

REGISTRATION DIVISION
Wichita, Kansas

Commission Expires:



WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company-NATIONAL COOPERATIVE REFINERY ASSN.
Farm- Valonta No. 6

SEC. 31 T. 16 R. 11W
SW NE NE

Total Depth. 3346
Comm. 12-6-53 Comp. 12-17-53
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 2-6-54

County Barton
KANSAS



CASING:
8 5/8" 750' oem. w/400 sx
6 1/2" 3344' oem. w/185 sx

Elevation. 1905'

Production. 198 BO & NW

Figures Indicate Bottom of Formations.

rock clay & sand	70
shale, shells, sand	
strks	486
red bed	744
anhydrite	770
shale & shells	1175
shale & salt	1325
shale " lime	1415
shale & shells	1490
lime & shale	2032
lime	3060
lime & shale	3170
lime	3311
reagan sand	3325
sand	3346
Total Depth	

TOPS:	
Huebner	2935
Toronto	2950
Douglas	2978
Brown Lime	3032
Lansing	3050

K. G. S. LIBRARY

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1957

CONSERVATION DIVISION
Wichita, Kansas