


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 N. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 21 Twp. 22 Rge. (E) 25 (W)  
Location as "NE/CNWxSWx" or footage from lines NW NW NW  
Lease Owner Pickrell Drilling Company  
Lease Name Wolfinger Well No. 1  
Office Address 705 Fourth National Bank Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9/8/1959  
Application for plugging filed 9/8/1959  
Application for plugging approved 9/8/1959  
Plugging commenced 9/8/1959  
Plugging completed 9/8/1959  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4755 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 375', bridge hole and cement with 30 sacks cement.  
Then heavy mud to 205', set second plug and cement with 10 sacks cement.  
Then heavy mud to 35', set plug and cement to bottom of cellar.

Plugged rat hole top to bottom with cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1959

9-16-59

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building

STATE OF Kansas COUNTY OF Sedgwick, ss.  
C.W. Sebitts

C.W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.W. Sebitts  
705 Fourth National Bank Building  
(Address)

SUBSCRIBED AND SWORN to before me this 15 day of September, 19 59

My commission expires October 15, 1962

Judith L. Palmer  
Judith L. Palmer Notary Public.

PLUGGING

File Sec. 21 T 22 R 25W  
Book Page 3 Line 25

**ROTARY DRILLING LOG**

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas

Rotary Drilling Commenced 8/23/59

LOCATION: NW NW NW 21-22-25w  
Hodgeman County, Kansas  
#1 WOLFENGER

Rotary Drilling Completed 9/8/59

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD:  
200' (9 jts.) 8 5/8" O.D. surface casing, cemented with 100 sacks, 2% gel, cement circulated.  
Bottom plug to 375', 30 sacks, thru drill pipe. Second plug 205', 10 sacks, plug thru drill pipe. Top plug 35' cemented to bottom of cellar @ 10:00 AM 9/8/59.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40'	Surface soil and shale	Circ. for samples:
200'	Shale and clay	
285'	Sand, rock and shale	4720'
1100'	Shale and shells	4485'
1620'	Red bed, shale and shells	4609'
1700'	Red rock, shale and shells	4665'
1735'	Anhydrite	4675'
2060'	Shale and shells	4685'
2740'	Lime and shale	4700'
3085'	Lime	4713'
3605'	Lime and shale	
3705'	Lime	
3910'	Lime and shale	
3980'	Lime	
4015'	Lime and shale	
4205'	Lime	
4240'	Lime and shale	
4658'	Lime	
4755'	Mississippi	
4755'	R.T.D.	

Slope Test:

2000' 0°  
3000' 0°  
4000' 0°

S. L. M.

2000' OK  
3000' OK  
4000' OK

**PLUGGING**

Loc. No. 21 T 22 R 25W  
Book Page 3 Line 25

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP 16 1959  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
Attorney-in-Fact  
C. W. Sebitts, Partner

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 10th day of September, 19 59, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: October 15, 1962

[Signature]  
Notary Public  
Judith L. Palmer