


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
12 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 2 Twp. 22S Rge. 25W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Fehrenbach Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 6, 1960

Application for plugging filed April 6, 1960

Application for plugging approved April 6, 1960

Plugging commenced April 6, 1960

Plugging completed April 6, 1960

Reason for abandonment of well or producing formation No commercial quantities
of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 550' with 20 sacks of
cement; Set second plug at 215' with 20
sacks of cement; Set top plug at 40' with
10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. J. Boone

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God IMPERIAL OIL OF KANSAS, INC.

(Signature) BY: [Signature] Pet. Engr.

780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1960.

My commission expires July 7, 1962

[Signature]
Notary Public.



DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

Fehrenbach No. 1
C NW SE Sec. 2-22S-25W
Hodgeman County, Kansas

Total Depth: 4675'

Commenced: 3-22-60 Completed: 4-6-60

Elevation: 2471' R.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 225' with 175 sacks cement.

Figures indicate bottom of formations:

			<u>TOPS</u>	
Shale & Rock	226'			
Shells, Sand & Shale	375'	Heebner	3888'	(-1417)
Shale & Sand	1150'	Lansing	3973'	(-1502)
Dakota Sand	1350'	Cherokee	4466'	(-1995)
Shale & Sand	1720'	Mississippi	4477'	(-2006)
Shale	1970'	Rotary Total Depth	4675'	(-2204)
Shale & Lime	3950'			
Lime	4675'			
Total Depth	4675'			

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: K. J. Boone
K. J. Boone-Pet. Engr.

Subscribed and sworn to before me this 15th day of April, 1960.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier-Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1960

CONSERVATION DIVISION
Wichita, Kansas